

Model SUSMP Training for Municipal Staff and Plan Checkers

Monday, June 1, 2009

City of San Diego Metropolitan Wastewater Department Auditorium
9192 Topaz Way, San Diego



Sara Agahi, PE, CFM
County of San Diego

Agenda

- Introductions and Overview of the SUSMP Process and Objectives (Agahi)
- Using Low Impact Development to Meet NPDES Treatment and Hydrograph Modification Management Requirements (Cloak)
- Review of the 2009 Model SUSMP and Changes from the 2001 SUSMP (Cloak)
- Using the LID Design Guide (Chapter 4) to Prepare and Review Project Submittals (Cloak)
- Integrating Hydromodification Management into the SUSMP and the IMP Sizing Calculator (Cloak)
- Summary, Next Steps, and Additional Questions (Agahi)

Overview of SUSMP Process

- San Diego Regional Water Quality Control Board adopted updated stormwater permit January 24, 2007
- New SUSMP requirements
 - Copermittees individually update Local SUSMPs by January 2008
 - Copermittees collectively submit Draft Model SUSMP by July 2008

Local SUSMP update requirements

- Removal of obsolete or ineffective BMPs
- Incorporation of Low Impact Development (LID) and source control BMPs
- Addition of LID treatment control BMPs (such as bioretention cells, bioretention swales, etc)
- Update definition of Priority Development Projects (PDPs)
 - commercial development > 1 acre
 - Addition of retail gasoline outlets ≥ 5000 ft² and ADT of 100+ vehicles
- Updated Treatment Control BMP Selection Matrix Table and discussion with more recent Caltrans and CASQA studies

Model SUSMP update requirements

- Define minimum LID and BMP requirements and standards to maximize use of LID practices and principles as a means of reducing stormwater runoff
- Establishment of siting, design, and maintenance criteria for LID and treatment control BMPs so that they are constructed correctly and are effective at pollutant removal and/or runoff control

Implementation of Model SUSMP: Timeline

- Jan 24, 2007: Regional Board adopts new permit
- Copermittees work collaboratively to update local SUSMPs and begin work on Model SUSMP update, via Land Development Workgroup; continue to meet regularly
- Copermittees contract with Brown and Caldwell to update Model SUSMP and develop Hydromodification Management Plan (HMP)
- Jan 24, 2008: Copermittees update local SUSMPs
- July 24, 2008: Copermittees submit draft Model SUSMP to Regional Board for Approval
- September 18, 2008: Regional Board provides comments and NRDC comments
- Jan 21, 2009: Copermittees re-submit draft Model SUSMP to Regional Board for Approval
- March 25, 2009: Regional Board finds Model SUSMP Adequate

Implementation of Model SUSMP: Timeline

- April 22, 2009: NRDC/San Diego Coastkeeper request San Diego Board hold a hearing on the acceptance of the Model SUSMP
- April 22, 2009: NRDC/SDC concurrently file petition for review with State Board, but request abeyance for 6 months pending response from the Regional Board
- 2007: NRDC submitted petition for review to State Board regarding the issuance and terms of San Diego permit; elected to hold in abeyance.
- May 15, 2009: San Diego Board denies NRDC/SDC request to hearing
- Now: NRDC/SDC to determine whether they will activate both related petitions

Implementation of Model SUSMP: Timeline

- By March 25, 2010: Copermittees must have incorporated Model SUSMP changes into Local SUSMPs
- Between now and then:
 - Additional trainings
 - Consultant team developing sizing tool to assist with LID and HMP design


How Does this Relate to HMP?

- Copermittees submitted draft HMP to Regional Board January 21, 2009
- Expecting RB comments within next month or so
- Copermittees will have 6 months to finalize the HMP and then re-submit to RB
- Assuming RB approves plan with no additional comments, Copermittees have additional 6 months to incorporate requirements into local SUSMPs

For more information...

- All related Copermittee documents, submittals to Regional Board, etc., are located at:

<http://www.projectcleanwater.org>



Project Clean Water

Go to: Standard Urban Stormwater Management Plan (SUSMP)
and Hydromodification Workgroup page